156
08/18/15

10'x5' PRECAST CONCRETE CULVERT

PROJECT NO. L-C(N48)--73-97

WOODBURY COUNTY

Letting Date SEPTEMBER 8, 2015

IOWA
DEPARTMENT OF TRANSPORTATION

Project Development Division

PLANS OF PROPOSED IMPROVEMENT ON THE

SECONDARY ROAD SYSTEM
WOODBURY COUNTY
10'x5' PRECAST CONCRETE CULVERT
PROJECT NO. L-C(N48)--73-97

Miller Township On 240th Street North Line Sec. 17, T87N, R43W

The Iowa Department of Transportation Standard Specifications for Highway and Bridge Construction, series of 2012, plus current Supplemental Specifications and Special Provisions shall apply to construction work on this project.

Plus Current Special Provisions and Supplemental Specifications

TRAFFIC CONTROL PLAN

THIS ROAD WILL BE CLOSED TO THROUGH TRAFFIC DURING CONSTRUCTION. TRAFFIC ROUTES ADJACENT TO PROPERTIES WILL BE MAINTAINED AS PROVIDED FOR IN ARTICLE 1107.08 OF THE CURRENT STANDARD SPECIFICATIONS. TRAFFIC CONTROL DEVICES, PROCEDURES, LAYOUTS, SIGNING, AND PAVEMENT MARKINGS INSTALLED WITHIN THE LIMITS OF THIS PROJECT SHALL CONFORM TO THE "MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES FOR STREETS AND HIGHWAYS" AS ADOPTED BY THE DEPARTMENT PER 761 OF THE IOWA ADMINISTRATION CODE (IAC) CHAPTER 130.

MAINTENANCE OF SIGNS AND BARRICADES AS STATED IN ARTICLE 1107.09 SHALL APPLY ON THIS PROJECT.

SIGNING ON THIS PROJECT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR AND SHALL BE IN ACCORDANCE WITH ROAD STANDARD TC-252

Approved

Board of Supervisors

LICENSED PROFESSIONAL ENGINEER MARK J. NAHRA 11452 IOWA

I hereby certify that this engineering document was prepared by me or under my direct personal supervision and that I am a duly licensed Professional Engineer under the laws of the State of Iowa.

8/19/2015
Date

Iowa Registration Number 11452
Expiration Date 12/31/2016

Pages or sheets covered by this seal:
Pages A1, A2, B1, C1, D1

2011 AADT 10 V.P.D.

Project Number: L-C(N48)--73-97

INDEX OF SHEETS

No.	Description
A1	TITLE SHEET
A2	LOCATION MAP
B1	ESTIMATE OF QUANTITIES AND GENERAL INFORMATION
C1	PRECAST RCB CROSS SECTION
D1	SITUATION PLAN

ROAD STANDARD PLANS

The following Standard Plans shall be considered applicable to construction work on this project.

Identification	Date	Identification	Date	Identification	Date
EW-101	10-20-15				
EW-401	10-20-15				
TC-252	10-20-15				

RCB STANDARDS

(May be obtained at Bridge Design Services)

Standard	Date Issued	Date Revised	Standard	Date Issued	Date Revised
RRCB 01-13	JANUARY, 2013		PES 4-13	JANUARY, 2013	
RRCB 02-13	JANUARY, 2013				
RRCB 10-13	JANUARY, 2013				
PES 1-13-13	JANUARY, 2013				
PES 3-13-13	JANUARY, 2013				