HMA RESURFACING & COLD-IN-PLACE RECYCLING

PROJECT NO: FM-CO97(136)--55-97

WOODBURY COUNTY

Letting Date MARCH 19, 2019

IOWA
DEPARTMENT OF TRANSPORTATION

Highway Division

PLANS OF PROPOSED IMPROVEMENT ON THE

FARM TO MARKET SYSTEM
WOODBURY COUNTY
HMA RESURFACING &
COLD-IN-PLACE RECYCLING
PROJECT NO: FM-CO97(136)--55-97

The Iowa Department of Transportation Standard Specifications for Highway and Bridge Construction, Series 2015, plus applicable General Supplemental Specifications, Developmental Specifications, Supplemental Specifications and Special Provisions, shall apply to construction on this project.

D38: From K42 to K64 HMA Rehab and Resurfacing

Project Number: FM-CO97(136)--55-97

INDEX OF SHEETS

No.	Description
1	TITLE SHEET.
2	LOCATION PLAN
3	ESTIMATE OF QUANTITIES AND GENERAL NOTES
4	ESTIMATE REFERENCE INFORMATION
5	TYPICAL SECTION AND DETAILS
6	TYPICAL DETAILS
7	TABULATIONS
	PLAN AND PROFILE AVAILABLE AT THE COUNTY ENGINEERS OFFICE

MILEAGE SUMMARY

Div.	Location	Lin. Ft.	Miles
	STA. 9+77 TO STA. 380+16.40	37,039.40	
	TOTAL LENGTH PROJECT FM-CO97(136)--55-97	37,039.40	7.015

ROAD STANDARD PLANS

The following Standard Plans shall be considered applicable to construction work on this project.

Identification	Date	Identification	Date	Identification	Date
BA-200	10-18-16	PM-110	10-16-18	TC-252	04-18-15
BA-221	04-18-17	PM-120	10-21-14		
BA-225	10-17-17	PV-10	04-19-11		
BA-260	10-18-16	TC-202	04-21-15		
BR-101	04-21-15	TC-212	04-16-13		
BR-104	10-17-17	TC-214	10-17-17		

TRAFFIC CONTROL PLAN

THIS ROAD WILL BE OPENED UNDER FLAGGER AND PILOT CAR OPERATIONS FOR THROUGH TRAFFIC DURING HMA CONSTRUCTION, AND WILL BE CLOSED FOR BRIDGE APPROACH CONSTRUCTION. TRAFFIC ROUTES ADJACENT TO PROPERTIES WILL BE MAINTAINED AS PROVIDED FOR IN ARTICLE 1107.08 OF THE CURRENT STANDARD SPECIFICATIONS. TRAFFIC CONTROL DEVICES, PROCEDURES, LAYOUTS, SIGNING, AND PAVEMENT MARKINGS INSTALLED WITHIN THE LIMITS OF THIS PROJECT SHALL CONFORM TO THE "MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES FOR STREETS AND HIGHWAYS" AS ADOPTED BY THE DEPARTMENT PER 761 OF THE IOWA ADMINISTRATION CODE (IAC) CHAPTER 130.

MAINTENANCE OF SIGNS AND BARRICADES AS STATED IN ARTICLE 1107.09 SHALL APPLY ON THIS PROJECT.

SIGNING ON THIS PROJECT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR AND SHALL BE IN ACCORDANCE WITH ROAD STANDARD TC-202, TC-212 TC-214 AND TC-252.

Approved

Board of Supervisors

LICENSED PROFESSIONAL ENGINEER
MARK J. NAHRA
11452
IOWA

I hereby certify that this engineering document was prepared by me or under my direct personal supervision and that I am a duly licensed Professional Engineer under the laws of the State of Iowa.

Mark J. Nahra 11/20/2018
Date

Iowa Registration Number 11452
Expiration Date 12/31/2020

Pages or sheets covered by this seal:
Pages 1, thru 7

IOWA ONE CALL
1-800-292-8989
www.iowaonecall.com
811 Know what's below. Call before you dig.

2015 AADT 470 V.P.D.